

Army Public School Beas  
PO : Dhilwan  
Distt: Kapurthala  
Punjab : 144804

1513/APS/Visitors Room


24 Apr 2024

**CALL FOR QUOTATIONS: CONSTRUCTION OF NEW WASHROOM FOR VISITORS ROOM BY APS BEAS FOR THE FY 2023-24**

Dear Sir/Madam,

1. This school intends to construct a new washroom for visitors room by APS Beas for the FY 2023-24. You are requested to send your quotations in a sealed envelope for the said work as per description attached to this letter.
2. Quotations will be opened at **1100 hrs on 10 May 2024** at HQ 55 (I) Mech Bde and no quotation will be received after **1100 hrs**.
3. All dealers/contractors are welcome to be present at the time of opening of quotations.
4. The work should be completed within 21 days from the date of placing work order.
5. Please ensure that the rates are quoted in the letter calling for quotations/letter pad.
6. The rates should be quoted exclusive of Central/State sales tax/octroi charges/excise duty or any other taxes as applicable which will be indicated separately. In case you fail to comply with requirements, rates quoted by you will be taken as inclusive of all such taxes, if any.
7. Payment will be made online through RTGS by HDFC Bank Branch Beas. Please quote your bank details with IFSC Code for our n/a.
8. Please mention TIN/CST/GST No in your quotation.
9. Please also mention "Construction of New Washroom FOR Visitors Room" on the top outside of envelope.
10. Vendors are requested to visit the school and see the site before quote their rates. No amendment will be accepted after last date of submitting of quotations.
11. No advance payment will be made and entire payment will be made once work assessment is done by BOO/ Engr rep.
12. If the construction is not completed after 21 days from the date of work order, you will be charged 0.5% per week of the total value of concerned project cost and not more than 10% of the total cost of the project.

Yours faithfully,

  
(Pankaj Verma)  
Bursar

**CALL FOR QUOTATIONS: CONSTRUCTION OF NEW WASHROOM FOR VISITORS ROOM BY APS BEAS FOR THE FY 2023-24**

S. No	Description/ Scope of Work	Qty	Total amount
(a)	Demolishing work	01	
(b)	Civil work - Erection of new walls and RCC slab to be casted, - repair on wall & floor (Rough plaster for tiles on walls & floor and counter slab)	Job	
(c)	Removal of malba		
(d)	Piping & wiring of sanitary work. (finolex)		
(e)	Sanitary fittings (Jaguar basic range) Counter wash basin -1 No, wall hung WC - 1 No and Unrinal - 1 No, Sanitary fittings (Jaguar basic range), Taps - 1 hand faucets - 1 No		
(f)	Electrical wiring & piping (ISI mark)		
(g)	Electrical lighting LED panel 8 watt - 4 No (Jaguar), switches (Havells), wall fans - Orient - 1 No, Exhaust fans Orient - 1 No		
(h)	Tiles on walls (Vitrified tiles) (size: 4'-0" x 2'-0"). Till 7'-0" height		
(j)	Tiles on floor (Volento), (size: 2'-0" x 2'-0") anti skid		
(k)	Tiles labour & material		
(l)	Black granite on counter slab		
(m)	Aluminium heavy gauge doors (2pc) with material & labour and granite chowkat - 1 No (on main entrance door of washroom).		
(n)	Glass work - Looking glass - 2 No, glass partition between urinal - 1 No		
(o)	Paint work on walls and ceiling (emulsion with putty and primer)		
(p)	GST		
(q)	Freight		
(r)	Any other charges, if applicable		
(s)	Total		

Signatures \_\_\_\_\_  
 Name & Place/Address of firm with stamp  
 Mobile No-

